



*Public Works and Engineering Departments: 847-716-3568*

DATE: May 25, 2022

Dear Residents:

The Village has awarded this year’s road rehabilitation program to A Lamp Concrete Contractors, Inc., of Schaumburg, Illinois. The roads listed below will be under construction this year:

<u>Street</u>	<u>Limits</u>	<u>Work</u>
<b>Sunview Lane</b>	from Hibbard Road to West End	Water Main/Rehab
<b>Locust Road</b>	from Sunset Road to Mt Pleasant Rd	Water Main/Rehab
<b>Merrill Street</b>	from Gordon Terr to Green Bay Rd	Water Main/Rehab
<b>Gage Street</b>	from Gordon Terr to Green Bay Rd	Water Main/Rehab
<b>Maple Street</b>	from Ash St to Elm St	Resurfacing
<b>Tower Road</b>	from Forestway to Village Limits	Resurfacing
<b>Tower/Hibbard Road</b>	at the intersection of Tower Road/Hibbard Road	Sidewalk Improvement

Rehabilitation and reconstruction work will include milling the existing surface, removing, replacing or repairing curbs, and resurfacing. Minor storm and sanitary sewer structure repair will also be performed as necessary. The project will include construction of new water mains on Sunview, Locust, Gage, and Merrill and disconnecting existing water services from smaller or older water mains while installing new services to the new, larger water mains.

The stages of construction are as follows:

- The pavement will be saw-cut in preparation for any necessary storm and sanitary sewer repairs, water service construction, water main construction, and/or curb repair.
- All necessary storm and sanitary sewer and water service/main work will commence. This may include removing and replacing storm and sanitary manholes; storm catch basins and inlet structures; and any necessary storm and sanitary sewer repair/replacement.
- Curb repair/replacement, which will include localized removal and replacement of concrete curb and gutter, will follow.
- After the sewer work and curb repair has been completed, all roads scheduled for rehabilitation will be milled and resurfaced.

Additional notices will be passed out ahead of construction in impacted areas.

Minor traffic delays may be experienced throughout the duration of the project. During construction taking place on your street, please do not park your vehicles on the road,

as you will have access to your driveways during most of the construction process. If curb work is scheduled across your driveway apron (for which you will be notified), this will require that you remove vehicles from your property, at which time you will receive further instruction for off-site parking. Please instruct any landscaping or other contractors that may be doing work on your property that no parking will be allowed on the street during construction from 7 AM to 7 PM. Parking on the adjacent streets, as permitted by the signage, may be necessary.

Please note that all work will be performed within the Village right-of-way areas. **If you have any type of existing private features within the Village right-of-way areas (i.e. sprinkler systems, landscape features, landscaping boulders, etc.), they should be deactivated and/or removed as soon as possible and stored on your property to ensure that damage does not occur to these items.** The Village **will not** repair or replace private appurtenances left within the Village right-of-way.

Due to the scope, complexity, and nature of the project, as well as the unpredictability of weather, some delays and disruptions may occur. We ask for your understanding during these times. If you are planning a special event such as a wedding or large party during the summer, please contact us so that we can accommodate your needs as much as possible.

If you have any questions regarding these matters, please feel free to contact Obaid Khalid, Civil Engineer, at 847-716-3530 or [okhalid@winnetka.org](mailto:okhalid@winnetka.org) or James Bernahl, Director of Engineering, at 847-716-3261 or [jbernahl@winnetka.org](mailto:jbernahl@winnetka.org). Thank you for your patience during the completion of the planned improvement to our Village.

Sincerely,

Winnetka Engineering Department